Abstract Enterprises Security Systems, Inc.
Licensed Low-Voltage Contractor | NYS Lic. #12000287431
Brooklyn • Bronx • Queens • Manhattan • Long Island • Hudson Valley

(800) 486-0943
support@abstractenterprisessecuritysystems.com
abstractenterprisessecuritysystems.com

PROPOSAL

Single Phase: 31 UniFi Cameras, Card/Fob Access on 2 Doors, G6 Pro Entry Door Buzzer

Prepared for	A1 Party NYC	Proposal no.	AESS-2026-1028-A1-SP
Project address	1900 Linden Blvd, Brooklyn, NY 11207	Date	October 28, 2026
Contact	Sam • samf@a1partynyc.com	Valid through	November 27, 2026
		Reference	Your scope of work, A1_Camera_Scop

OVERVIEW

This is the single-phase job you laid out in your scope of work: 31 UniFi cameras, card/fob access on the Sheffield Ave and Georgia Ave doors, a G6 Pro Entry buzzer at the customer door and 20 fobs, all installed in one visit and one lift week. The recorder, switches and battery backup go in the upstairs closet, with a second switch midway along the Georgia wall on a fiber uplink so the Georgia-side devices stay on short runs. Everything is recording and tested before the crew leaves.

INVESTMENT

ITEM	QTY	AMOUNT
UniFi G6 Pro Bullet 4K cameras, installed UVC-G6-Pro-Bullet. One per truck door aimed at incoming trucks for faces, plates and two-way talk (D1 to D4), plus the 4 rack aisles and main aisle	9	$6,066.00
UniFi G6 Bullet 4K cameras, installed UVC-G6-Bullet. Crisscross camera at each truck door (4), yard gate on the Georgia-side roof edge (1), back aisle (1)	6	$2,364.00
UniFi G6 Turret 4K cameras, installed UVC-G6-Turret. Staging, returns, H slab and wood shop (6), the safe (1), cage-room door (1)	8	$3,152.00
UniFi G5 Turret Ultra cameras, installed UVC-G5-Turret-Ultra. Office, stairs, upstairs and time clock (6), laundry room (1)	7	$2,268.00
UniFi G6 PTZ camera, installed UVC-G6-PTZ. Georgia-side roof edge, auto-tracks the yard, two-way talk	1	$594.00
UniFi NVR G2 Pro recorder, installed UNVR-G2-Pro. Upstairs closet, UniFi Protect set up on your phones and computers, console registered to A-1	1	$999.00
UniFi 24TB enterprise drives UACC-HDD-E-24TB. About 3 months of recording	4	$3,996.00
UniFi Switch Pro Max 48 PoE USW-Pro-Max-48-PoE. Main switch in the upstairs closet	1	$1,299.00
UniFi Switch Pro Max 24 PoE, Georgia wall, installed USW-Pro-Max-24-PoE. Midway along the Georgia wall by staging, serving the 15 Georgia-side devices	1	$994.00
Fiber uplink to the Georgia-wall switch, installed Single fiber run from the upstairs closet with 10G optic modules	1	$428.00
UniFi UPS 2U battery backup UPS-2U-US. Keeps the recorder and switches running through outages	1	$279.00
UniFi Access card/fob doors, installed Sheffield Ave and Georgia Ave doors: UA-G3 reader, UA-Hub-Door (powers the lock), electric strike, exit button	2	$1,752.00

UniFi G6 Pro Entry door buzzer, installed UVC-G6-Pro-Entry at the customer door. Visitors buzz; you view, talk and unlock from the app (see clarifications)	1	$574.00
UniFi Access key fobs UA-Pocket	20 fobs	$198.00
Runs over 100 ft D1, D2, D3, D4, W3, W4 and the Sheffield Ave door, each billed as an additional home run	7	$1,365.00
Scissor lift rental, 1 week 26 ft electric scissor lift, delivered and picked up	1 week	$1,187.00

Subtotal	$27,515.00
NYC sales tax (8.875%)	$2,441.96
Total	**$29,956.96**
Deposit due to schedule (50%)	$14,978.48
Balance due upon completion	$14,978.48

OPTIONAL ADD-ONS

1. Drive Protection Plan, 2 years: $149.00 — covers a replacement drive (same or larger), the tech visit and labor, reformat and recording restored; or $6/month per recorder
2. Drive Protection Plan, 3 years: $219.00 — same coverage; buy at install or within 30 days, AESS-supplied drives only, 1 replacement per year
3. Extended warranty, 1 year (covers labor): $2,752.00 — labor to diagnose, remove and replace a covered part
4. Extended warranty, 2 years (covers labor): $4,953.00
5. Extended warranty, 3 years (covers labor): $7,429.00

SCOPE OF WORK

1. Mount 4 G6 Pro Bullets at truck doors D1 to D4 aimed at incoming trucks, and a crisscross G6 Bullet at each of those doors.
2. Mount the G6 PTZ and the yard-gate G6 Bullet on the Georgia-side roof edge, aimed into the yard.
3. Mount 5 G6 Pro Bullets down the 4 rack aisles and the main aisle, 6 G6 Turrets over staging, returns, the H slab and the wood shop, a G6 Bullet on the back aisle and a G5 Turret Ultra in the laundry room.
4. Mount 6 G5 Turret Ultras in the office, stairs, upstairs and at the time clock, plus G6 Turrets on the safe and the cage-room door.
5. Install the NVR G2 Pro with 4 x 24TB drives, the Switch Pro Max 48 PoE and the UPS in the upstairs closet; install the Switch Pro Max 24 PoE midway along the Georgia wall by staging with a fiber uplink from the closet.
6. Run a dedicated Cat6 home run from every device to its switch; terminate, label and test every run.
7. Install UniFi Access card/fob hardware on the Sheffield Ave and Georgia Ave doors (reader, door hub, electric strike, exit button) and enroll 20 fobs.
8. Install the G6 Pro Entry at the customer door shown by Mendel on site.
9. Set up UniFi Protect and Access with the console registered to A-1, set recording, alerts and user access, and walk your team through the app before we leave.

CLARIFICATIONS & EXCLUSIONS

1. Single phase: everything on this proposal is installed in one visit and one lift week, and the system is recording and tested before the crew leaves.
2. Run lengths: 7 runs over 100 ft are priced, based on your camera map with the second switch midway along the Georgia wall. Every run that measures over 100 ft on site is billed as an additional home run; if more than 7 do, each additional one is $195, confirmed in writing before it is pulled.

3. Customer door buzzer: the G6 Pro Entry unlocks a door only when it is installed on a door with UniFi Access hardware. If it goes on the Sheffield Ave or Georgia Ave fob door, it serves as that door's reader and the G3 reader on that door is credited. If it goes on a separate customer door, the door hub, electric strike and exit button for that door are added by written change order before that work is done.
4. Yard cameras assume a clear sight line from the Georgia-side roof edge; we confirm it on day one. If the roof cannot see the yard, the beamed WiFi option is priced in writing before that work is done.
5. Electric strikes are priced for standard single doors with an existing frame. Glass, metal-frame or double doors that need a mag lock or other hardware are quoted before that work is done.
6. Excluded: 120V electrical work, roof penetrations requiring a roofer, and wall patching and painting. Roof access is provided by the client.
7. Internet service and router are supplied by the client; remote viewing and alerts require a working internet connection.
8. Equipment and scheduling: equipment is ordered once the deposit clears. As of October 28 Ubiquiti lists the NVR G2 Pro restocking November 2 and the 24TB enterprise drives sold out with no restock date. Your install week is booked once all equipment is in hand, so the job is completed in a single visit. If the 24TB drive stays unavailable, we substitute equivalent recording capacity at no change in price.
9. Ordered equipment is non-refundable.
10. Site access: an adult with access must be on site for the full 2-hour arrival window with a working phone number on file. If no one provides access within 30 minutes of the technician's arrival, the visit is a No-Access Visit and a trip charge equal to the area service-call fee applies (Agreement Section 12).
11. Internet and network: the Client supplies working internet and a router or switch with enough free ports for every device. If the router is full or not working, we can supply a switch by change order, or a return trip is billed as a new service call; the invoice remains due in full (Agreement Section 13).
12. Recording time, night vision range and remote viewing depend on camera settings, motion, lighting and the Client's internet upload speed.
13. Door hardware is priced for doors and frames in good working order. Damaged, misaligned or non-standard doors, frames or closers, locksmith work, and landlord or building approvals are the Client's responsibility unless quoted.
14. Phone and app calling depend on each resident's phone, app permissions and internet service.
15. Door hardware is priced for doors and frames in good working order. Fire-code egress, fire-alarm tie-ins, locksmith work and building approvals are excluded unless quoted.
16. Cable runs are priced for open, accessible pathways. Plaster, brick, concrete, fire-stopped or inaccessible walls and runs over 100 ft are priced by change order before the work is done. Internet speed is set by the Client's ISP plan.
17. Any union, prevailing-wage, after-hours, insurance-certificate or building-access requirements not stated in this proposal are priced separately once provided in writing.
18. Equipment of equal or better specification may be substituted.
19. This proposal is valid for 30 days.

WARRANTY

Equipment is warranted for one year, parts only (hard drives 90 days), under the Abstract Enterprises Master Installation, Service & Warranty Agreement. Labor to diagnose or replace a part is billed as a service call unless an extended warranty is purchased. Warranty does not cover damage from surge, water, impact, tampering or work by others, and is suspended while a balance is open.

PAYMENT TERMS

1. 50% deposit ($14,978.48) is due to schedule the work. The balance ($14,978.48) is due upon completion.
2. Return trips and service calls after installation are billed at $195.00 per hour with a 3-hour minimum.
3. Invoices are issued through Housecall Pro with a secure online payment link. Late payments are subject to the terms of the Master Installation, Service & Warranty Agreement.
4. This proposal, together with the attached Master Installation, Service & Warranty Agreement (including its site-access, client-network and client-supplied-equipment terms), Terms of Service, Privacy Policy and Refund Policy, forms the agreement between the parties.

ACCEPTANCE

By signing below or paying the deposit, the client accepts this proposal and its terms.

Client signature

Date

Printed name

Abstract Enterprises Security Systems, Inc. — Anwar Timothy, President