ABSTRACT ENTERPRISES SECURITY SYSTEMS, INC.
(800) 486-0943 | support@abstractenterprisessecuritysystems.com

Low-Voltage Subcontractor Bid

Proposal #	AESS-2026-1030-MHLS	**Date**	October 30, 2026
Submitted to	Transitional Builders, Inc.	**Attn**	Ethel / Melody
Project	Mid-Hudson Library System	**Location**	103 Market St, Poughkeepsie, NY 12601
Bid due	End of day, Nov 6, 2026	**Valid**	60 days

Bid Summary (per Bid Form categories)

Bid Form Line	Scope	Amount
Demolition	Remove existing structured cabling system, all floors	$4,400.00
Communications: Structured Cabling	Cat6A horizontal cabling in 3/4" conduit stub-ups, Cat6A keystones, plates, patch panels, labeling, Fluke certification	$34,600.00
Communications: Data Communications	Fiber backbone between floors, AP and camera cabling, install owner-furnished APs, cameras and network gear, rack dressing	$11,800.00
Electrical: Fire Alarm/Security Devices	Disconnect, protect and reinstall existing fire/smoke detector components	$2,800.00
Bond	Performance bond allowance (removed if not required of subcontractors)	$1,600.00
	TOTAL BID	**$55,200.00**

Price includes NYS prevailing wage (Dutchess County, PRC #2026029144) and weekly certified payroll. Sales tax not included; project assumed tax-exempt per Owner.

Scope Included

• Removal of all existing structured cabling components throughout, per drawings.

• Up to 40 Cat6A cables (plenum-rated, premium manufacturer) from outlet locations to the data room / access-switch locations shown on ED-1, ED-2, ED-3, each in 3/4" conduit stub-up to above ceiling; outlets at 18" AFF unless noted.

• Data (1- and 2-jack), printer (PR), copier (CO), wireless access point (AP) and camera locations as shown.

• Cat6A keystone terminations at both ends, rated for 10 Gbps, faceplates, Cat6A patch panels and cable management.

• Fiber backbone between floors to the third-floor data room, with enclosures and terminations.

• Mounting and connection of owner-furnished access points, cameras, switches, firewall and NVR.

• Disconnect, store and reinstall existing fire/smoke detector components as noted on Sheet 1.

• Fluke certification of every Cat6A link and fiber strand, labeling, and as-built drawings.

• Rough-in and finish phases coordinated with the GC schedule.

Unit Prices (for count changes)

Item	Unit Price
Add / deduct one Cat6A drop (under 100 ft) in conduit, terminated and certified	$1,150.00 add / $650.00 deduct
Each run over 100 ft (charged as an additional home run)	$1,150.00

Exclusions

• Active network and security equipment (switches, firewall, routers, APs, cameras, NVR): furnished by Owner, installed by AESS.

• Line-voltage electrical work, power circuits and lighting.

• Patching, painting and wall/ceiling finish repair.

• Firestopping beyond AESS's own low-voltage penetrations.

• Work outside the drawings listed above; changes handled by written change order.

Schedule

Up to 12 working days on site across rough-in and finish phases, with a 2- to 3-technician crew. Our crew typically finishes ahead of this; the schedule is set conservatively so the GC never waits on low voltage.

Payment Terms

Deposit on award: all materials paid in full plus 50% of labor. Balance (remaining 50% of labor) due on completion. AESS will also work within the GC's subcontract billing schedule where it provides equivalent material funding. Credit card payments carry a 3% card fee.

Warranty

All materials supplied by AESS carry a 1-year parts warranty from completion (hard drives: 90 days). Owner-furnished equipment carries its manufacturer's warranty only. Labor after acceptance is billed separately unless an AESS extended warranty is purchased.

Cancellation Policy

Cancellation 72+ hours before the scheduled start: deposit refunded less a 25% scheduling/administrative fee. Under 72 hours: deposit non-refundable (may be applied to one reschedule within 30 days). Once technicians are on site or work has started, no cancellation; the full deposit is kept and completed work beyond the deposit is billed. Ordered materials are never refundable. No site access when scheduled counts as on-site.

Accepted by (Transitional Builders, Inc.)

Signature / Date: _____

Abstract Enterprises Security Systems, Inc.

Anwar Timothy, President